

Detailed Condition Assessment and Consultancy Services for Madinat Zayed Buildings, Al-Dhafra Region, Abu Dhabi. Lead Design Consultant Scope of Work (SOW)



Table of contents:

LEAD DESIGN CONSULTANT SCOPE OF SERVICES	3
---	----------

1. Acronyms, terms, and references	3
2. Scope of Work Stages	4
3. Project Information	4
3.1 Project Context:	4
3.2 Critical Project Drivers:	4
4. Scope of Work	5
4.1 General	5
4.2 Design Stages	6
4.2.1 Phase.01 – Detailed Condition Assessment & Technical Due Diligence (TDD).	7
4.2.2 Phase.02 – Strategic Recommendations and Feasibility Analysis.	8
4.2.3 Optional Scope of Work (To be priced in accordance with attached Fee Schedule)	9
4.2.3.1 Phase.03 (a) – Concept Design.	9
4.2.3.2 Phase.03 (b) – Schematic Design.	10
4.2.3.3 Phase.03 (c) – Detailed Design.	15
4.2.3.4 Phase.03 (d) – Tender Documentation and Tender Stage.	21
4.2.3.5 Phase.04 – Construction site supervision.	21
5. Commercial proposal and Fees schedule	23
5.1 Requirements	23

LEAD DESIGN CONSULTANT SCOPE OF SERVICES

1. Acronyms, terms, and references

Acronym or Term	Definition
TQD	TAQA Distribution Company
Employer/ Client	TAQA Distribution Company
LDC	Lead Design Consultant
AOR	Architect Of Record
ID	Interior Design
NDA	Non-Disclosure Agreement
PQQ	Pre-Qualification Questionnaire
UAE	United Arab of Emirates
OTT	Out Of Tender
CS	Customer Service
RFP(s)	Request for Proposal(s)
ADCD	Abu Dhabi Civil Defense
DOE	Department of Energy
HSE	Health, Safety & Environment
POD	People of Determination
FLS	Fire & Life Safety
MEP	Mechanical, Electrical, And Plumbing

Table 1: Acronyms, Terms, and Definitions

2. Scope of Work Stages

No.	Stage	Duration (Weeks)
1	Phase.01: Site survey, Assessments, and TDD	06 Weeks
2	Phase.02: Strategic Recommendations and Feasibility Analysis based on assessment findings	06 Weeks
3	Phase.03 (a): Concept Design	12 Weeks
4	Phase.03 (b): Schematic Design	06 Weeks
5	Phase.03 (c): Detailed Design	12 Weeks
6	Phase.03 (d): Tender Documentation and Tender Stage	06 Weeks
7	Phase.04: The post contract supervision and compliance monitoring services fees to be provided as monthly breakdown with resource allocation for projects programme. The post contract supervision and compliance monitoring services will be finalized at the end of the design stage only.	

3. Project Information

The Services to be performed by the Consultant in relation to the project include comprehensive building condition assessment, regulatory compliance evaluation, strategic recommendations, and full design services (including all specialist services) for three existing facilities requiring assessment, potential refurbishment, expansion, and/or reconstruction.

3.1 Project Context:

- Main Admin Building (1,200m²) located on Plot P100 (5,299.93m²).
- Customer Services Branch (150m²) located on Plot P100.
- Electrical Emergency Office (150m²) located on Plot P72 (4,717.63m²)

3.2 Critical Project Drivers:

- Achieving building legalization.
- Achieving full regulatory compliance with all the applicable authorities' requirements and building codes.
- Following DOE directive mandating 32% water and 22% electricity consumption reduction.
- Maintaining operational continuity during assessment and any construction.
- Achieving the required capacity expansion for additional staff with efficient workplace design.

4. Scope of Work

4.1 General

- (a) The Services encompass architectural and engineering assessment and design for building structure, envelope, and major systems including HVAC, plumbing, electrical, fire protection, with focus on occupied building operations and regulatory compliance.

Note: No aspects of the assessment, infrastructure evaluation, and building design required to provide fully functional, compliant facilities are to be excluded from the scope of Services unless specifically stated herein.

The following is a list of the main disciplines required to complete the assessment and design but is not intended to be exhaustive and does not imply any exclusion of a discipline not listed:

- Complete Building Condition Assessment (Structural, MEP, Envelope, Forensic Evaluation, Capacity assessment).
- Regulatory Compliance Assessment (For all applicable authorities requirements and building codes).
- Architectural Design.
- Structural Engineering.
- Mechanical.
- Electrical.
- Plumbing.
- Fire & Life safety.
- Civil engineering and Landscape architecture (site development, parking, roadways).
- Interior Design / Workplace Design.
- Façade assessment, design and maintenance.
- Infrastructure and Utilities Assessment and Design.
- Security, Access control, Surveillance.
- Security and Risk assessments.
- ICT, audio/visual, information technology, telecom, and low voltage design.
- Codes and approvals (including Building Legalization).
- Environmental.
- Sustainability and Energy Efficiency (DOE compliance).
- Lighting Design.
- Signage, Wayfinding, and Graphics.
- Vertical transportation engineering.
- Acoustic engineering.
- Waste management.
- Geotechnical review (if required for new construction or expansion) of soil reports, preparation of preliminary test pile design and liaising with the local authority.
- Architect of record.
- **Exclusions:**
 - Any design works other than for specified three buildings in Madinat Zayed and the related developments as based on the detailed assessment outcomes and the approved recommendations.

- (b) The Consultant shall complete the whole of the Services and each part of the Services at the times and within the periods stated above.
- (c) The Consultant shall in performing the Services take due account of TQD's primary objectives in relation to the Project (*Refer to the Critical project drivers*).
- (d) The Consultant shall co-operate, co-ordinate and liaise with other consultants appointed by TQD to provide professional services in relation to the Project including all without limitation.
- (e) The Consultant shall submit reports to TQD or its representative on its progress in the performance of the Services bi-weekly during assessment phase and monthly thereafter and in such form and with such detail as TQD may reasonably require.
- (f) The Consultant shall in performing the Services use its best endeavors to identify those technical and economic solutions which are most suited to the requirements of the Project to achieve an optimal design balancing regulatory compliance, operational requirements, budget constraints, and lifecycle costs.
- (g) The Consultant shall as be requested by TQD from time to time attend and participate in meetings with TQD Distribution stakeholders, operational teams, and other meetings held in relation to the Project and prepare minutes thereof where appropriate.
- (h) The Consultant shall in relation to the Project and at the appropriate times obtain all necessary consents, approvals, no objection certificates, permits (including without limitation building legalization documents, ADCD FLS certifications, DOE compliance certifications, the Preliminary Building Permit and the Final Building Permit) and the like from all relevant authorities and departments including preparing all documentation required in relation thereto and making all applications required therefor. Such authorities and departments shall include without limitation ADCD, DOE, ADM, Services authorities.
- (i) The Consultant shall ascertain and co-ordinate the requirements of all relevant authorities and departments in relation to the Project and, subject to the approval of TQD, shall incorporate all such requirements into the assessment recommendations and the design of the Project.
- (j) The Consultant shall consult and attend meetings as necessary with the relevant authorities and departments in relation to the Project and prepare minutes thereof where appropriate.
- (k) All assessments, recommendations, and designs prepared by the Consultant shall comply with all relevant regulations, codes of practice and by-laws for the time being in force.
- (l) The Consultant shall obtain all relevant information and data necessary to perform its obligations under this Agreement including without limitation existing buildings documentation.
- (m) The Consultant shall participate in value engineering exercises including attending value engineering workshops.
- (n) All deliverables at the respective stages described hereunder shall be submitted to TQD in soft copy.
- (o) The Consultant shall design to the budget set by TQD based on comparable benchmark projects and design guidelines provided by TQD.

4.2 Design Stages

The Consultant shall be responsible for the execution and delivery of the following

stages along with the associated deliverable items ensuring these are in line with TQD's project requirements and guidelines:

- **Phase.01** – Detailed Condition Assessment & Technical Due Diligence (TDD).
- **Phase.02** – Strategic Recommendations and Feasibility Analysis.
- **Phase.03 (a)** – Concept Design.
- **Phase.03 (b)** – Schematic Design.
- **Phase.03 (c)** – Detailed Design.
- **Phase.03 (d)** – Tender Documentation and Tender Stage.
- **Phase.04** – Construction site supervision.

4.2.1 Phase.01 – Detailed Condition Assessment & Technical Due Diligence (TDD).

- (a) The consultant shall perform comprehensive assessment of three existing Madinat Zayed facilities to determine existing conditions, building capacity, regulatory compliance status, capacity constraints, infrastructure adequacy, and development options.
- (b) The consultant shall attend meetings with TQD to discuss the technical due diligence report and revise/update any documents (as required).
- (c) The consultant shall include the below assessment Components – including without limitation:
 - **Building Legalization and Regulatory Compliance** – including without limitation: Building permits review, as-built vs. approved drawings comparison, regulatory compliance status across all authorities, NOC requirements, and legalization process.
 - **Structural Assessment** – including without limitation: Integrity evaluation, load-bearing capacity, foundation assessment, defects identification, seismic compliance, expansion feasibility, and remaining service life estimation.
 - **MEP Systems Assessment** – including without limitation: Mechanical (HVAC, BMS), Electrical (power distribution, lighting, emergency systems), and Plumbing/Drainage systems evaluation including capacity analysis for additional staff and DOE baseline requirements.
 - **Authorities' requirements and building codes compliance Assessment.**
 - **Building Envelope Assessment** – including without limitation: Exterior walls, roof, windows, glazing, thermal performance, waterproofing, and weatherproofing evaluation.
 - **HSE Workplace Safety Assessment** – including without limitation: workplace hazard identification, POD accessibility compliance, indoor environmental quality, and hazardous materials assessment.
 - **Energy Efficiency and Sustainability Assessment** – including without limitation: Energy/water consumption baseline, DOE compliance gap analysis, renewable energy opportunities, and sustainability potential.
 - **Infrastructure and Utilities Assessment** – including without limitation: Site utilities survey, capacity analysis for existing and future requirements, drainage, external lighting, and security systems.
 - **Parking and Site Circulation Assessment** – including without limitation: Current and future parking capacity analysis, circulation adequacy, POD compliance, and improvement opportunities.

- **Landscape and External Works Assessment** – including without limitation: Landscape condition, irrigation systems, external lighting, pedestrian circulation, wayfinding, and site furniture.
- **Space Planning and Capacity Analysis** – including without limitation: Space utilization efficiency, capacity analysis and workplace standards compliance.
- **Architectural and Interior Conditions** – including without limitation: Interior finishes, partitions, doors/hardware, accessibility compliance, wayfinding, and millwork condition assessment
- **Vertical Transportation Systems** – including without limitation: Elevator condition, capacity, performance, code compliance, and modernization requirements
- **Low Voltage and Technology Systems Assessment** – including without limitation: ICT infrastructure, structured cabling, data network, AV systems, security systems (CCTV, access control), and BMS

(d) Deliverables:

- Comprehensive Technical Due Diligence Report including critical findings, regulatory compliance status overview, key risks/constraints, preliminary recommendations, and budget implications.
- Building-by-Building Detailed Assessment covering all assessment components.
- Discipline-Specific Detailed Reports.
- Comprehensive Compliance Gap Analysis for ADCD Fire Life Safety, DOE Energy Efficiency, UAE Building Code, Workplace Safety, POD Accessibility, and Building Legalization — each including non-compliances classification, rectification scope, high level cost estimates, and implementation timeline
- Photographic Documentation organized by building, system/element, and condition with annotated descriptions
- Survey Drawings including as-existing measured drawings (site plan, floor plans, elevations, sections, roof plans), condition mapping overlays, and utility site plans
- Final Submission of all assessment reports, drawings and stage reports shall be submitted as soft copies (AutoCAD compatible files and PDF) as required. Detailed area breakdown showing the GFA, GIA, BUA with definitions.

4.2.2 Phase.02 – Strategic Recommendations and Feasibility Analysis.

- Based on Phase.01 findings, the Consultant shall develop comprehensive strategic recommendations and feasibility analysis comparing development options.
- The consultant shall attend meetings with TQD to discuss the findings and revise/update any documents (as required).

(c) Deliverables:

- The Consultant shall develop and analyze at least three (3) primary development options in comprehensive details, Each option shall include:
 - **Scope Definition:** Detailed description of works for all three buildings.

- **Technical Feasibility Analysis:** Regulatory compliance achievement, energy efficiency performance (DOE compliance), building performance/functionality, space efficiency/utilization, flexibility/future adaptability, technology integration capability, sustainability performance, asset condition/remaining service life.
- **Benefits and Constraints:** Clear identification of advantages and limitations.
- **Operational Analysis:** Operational disruption/business continuity, temporary relocation requirements, phasing/implementation complexity, maintenance requirements, facilities management complexity, staff accommodation during construction, customer service continuity.
- **Cost Estimate:** Detailed breakdown by building and discipline, Capital cost breakdown, lifecycle cost analysis (20-year horizon), operating cost comparison, ROI, payback period, cost per m²/occupant
- **Timeline:** Total project duration, design / approvals/ construction timelines, occupancy timeline, critical path analysis and phasing plan.
- **Risk Assessment:** Identification and evaluation of key risks.
- **Qualitative Comparison Analysis:** Workplace quality/staff satisfaction, customer experience enhancement, brand/image alignment, community/stakeholder perception, long-term asset value, future flexibility.
- The Consultant shall develop and provide preferred Option Recommendation, based on comprehensive comparative analysis, the Consultant shall recommend the preferred development option with clear justification.

Note on below Design and Implementation Phases: The Consultant shall include in their financial offer the following phases as optional scope items with detailed cost breakdown per stage.

Noting that TQD reserves the right to:

- Proceed with any or all of the optional stages based on budget availability and strategic decisions.
- Engage the Consultant for selected stages only.
- Negotiate scope and fees at the end of each completed stage based on refined scope and project requirements.

4.2.3 Optional Scope of Work (To be priced in accordance with attached Fee Schedule)

4.2.3.1 Phase.03 (a) – Concept Design.

- (a) Based on the approved preferred option from Stage 1, the Consultant shall develop the Concept Design to establish the design intent, spatial organization, and technical approach for the project. Concept Design Stage should include but is not limited to the following:
 - Development of concept Design options inclusive of all trades and renders (15 NOs).
 - Development of regulatory compliance strategy.
 - Development of sustainability and energy strategy.

- Development of a refined budget estimate ($\pm 15\%$).
- Pre-consultation meetings with relevant authorities; documentation of authority feedback and requirements, and incorporation of authority comments into design development.
- Attend meetings with TQD to discuss the Concept Design and revise/update any documents (as required).

(b) Deliverables:

- Concept design report inclusive of all the above-mentioned scope.

4.2.3.2 Phase.03 (b) – Schematic Design.

(a) The consultant shall commence the Schematic Design following receipt of TQD's approval on the Concept Design. Schematic Design Stage should include but is not limited to the following:

- Preface, including a description of the building and site.
- Area Calculations (Amenities, Gross, Net, Parking, Efficiency, etc.).
- Cost Report - clearly demonstrating the proposed design can be delivered within the project budget with an accuracy of $\pm 10\%$.
- Schedule of Finishes, FF&E and specifications for all design elements.
- Material boards both hard and digital copies.
- Assumptions, Design Criteria, Codes and Standards, local Service Provider and Statutory Authority design requirements for all systems, disciplines, and sub-consultant categories.
- Descriptions of design methodology and description of primary systems, with alternatives, for each discipline group.
- Identification of potential materials, systems and equipment and their criteria and quality standards.
- Investigation of availability and suitability of alternate materials, systems, and equipment. Coordination of similar activities for all disciplines.
- Analyze the advantages and disadvantages of the selected alternatives with the technical standards under consideration.
- Estimate service life and construction programme for each of the selected alternatives and technical standards.
- Environment Design Report, identifying the active and passive environmental conservation / management systems, including specific applications on design studies of the building (if required).
- Opportunities and Constraints.
- Ascertain all consents, approvals, no objection certificates, permits and the like needed to be obtained from all relevant authorities and departments and the procedures to be followed in relation thereto.

(b) The consultant shall attend design team meetings which to be held at weekly intervals in throughout the Schematic Design Phase. The meetings shall be chaired and minuted by the Consultant.

- (c) Obtain site investigation and topographic survey information and other relevant information commissioned by TQD.
- (d) Based on the approved Concept Design prepare and submit to TQD for review purposes a draft of the Schematic Design Phase documentation. All such documentation shall be marked "Draft".
- (e) The Schematic Design Documentation shall include as a minimum:
 - A final set of schematic design drawings including below grade levels, floor plans, building elevations and building sections.
 - Minutes of Design Team Meetings
 - 100% Schematic:
 - (i) **Site Plan: Scales vary but shall generally be 1:500:**
 - Site plan of the Project showing location of all buildings, roads, major mechanical/electrical equipment, parking, and landscaping elements.
 - Clear delineation of the Project limit lines preliminary spot elevations.
 - Proposed and existing utilities (if any) are noted.
 - Site drainage is indicated.
 - Site sections if needed to show overall relationship.
 - (ii) **Building Plans: Scales of 1:500, 1:200, 1:100, 1:50:**
 - Plans of all floors showing structural system, vertical transportation elements, core elements, vertical shafts, interior partitions, elevations.
 - Key dimensions, bay sizes and overall dimensions.
 - General notes indicating major extent of materials and any special condition or material.
 - Building sections are keyed.
 - Project limit lines noted if not otherwise clear.
 - Preliminary finish schedule.
 - Area summary.
 - (iii) **Roof Plans: Scales of 1:500, 1:200, 1:100:**
 - Roof materials.
 - Drains and slopes.
 - Major roof mounted equipment.
 - (iv) **Building Sections: Scale of 1:200, 1:100:**
 - Sections through buildings to show all relevant conditions including vertical transportation and adjacent conditions.
 - Floor to floor heights.
 - Ceiling heights.
 - Typical wall sections keyed.
 - Details (if any) shall be keyed.

(v) Building Elevations: Scales of 1:200, 1:100:

- All major elevations with extent of glazing and mullion spacing indicated.
- All materials called out in notes.
- Floor lines indicated.
- Overall dimensions.
- Setbacks and overhangs indicated (shadows, notes etc., 3-D views may be required).
- Relationships to existing and new finished grades clearly shown.

(vi) Schematic Details: Scales of 1:50, 1:10, 1:5:

- Preliminary wall sections at building perimeter.
- Relevant installation details of exterior materials.
- Partial elevations indicating materials and their inter-relationships.

(vii) Structural: Scales vary:

- Structural system description (with alternates, if applicable).
- One line floor and roof framing plans.
- Typical member sizes noted.
- Lateral load system noted.
- Design criteria.
- Details of any special conditions (large spans, trusses, cantilevers, etc.).

(viii) MEP: Scales vary:

- Preliminary systems are selected.
- Energy sources are identified, entrances are noted on architectural backgrounds.
- Preliminary equipment layouts.
- Vertical shafts and risers spaces are sized and coordinated with architectural drawings.
- Preliminary riser diagrams.
- Double line diagrams of all mechanical and electrical systems are shown on architectural backgrounds.
- Design criteria for the various systems are outlined.
- Applicable and governing codes are identified.
- Major service rooms and spaces are identified and shown on architectural drawings.
- Descriptions of mechanical systems including energy sources, District Cooling Company considerations, HVAC loads, energy conservation factors, special mechanical and process systems, systems descriptions, impact on other disciplines

and special Code requirements.

- Assumptions, Design Criteria, and Calculations.
- Plumbing and Drainage schematics.
- Description of plumbing and drainage needs, including potable, firefighting, and irrigation.
- Water distribution systems and storage requirements, drainage collection systems and sanitary sewers, load requirements versus availability.
- Supporting cost studies and analyses for design alternatives.
- Description of electrical load requirements, distribution concepts, lighting level requirements and emergency power requirements and grounding and lightning protection.
- Low voltage systems, including a brief description of building access control, security and surveillance, electronic locks, computer needs, telecommunication requirements (including information technology), data transmission and telephone systems, CCTV, audio-visual, CATV and antenna requirements, and grounding/lightning protection considerations.

(ix) Fire and Life Safety submittal shall include, but are not limited to, the following:

- Description of fire detection and protection systems, smoke detection systems, sprinkler systems, fire zones and compartmentalization.
- Supporting cost studies and analyses for design alternatives.
- Calculations and assumptions.
- Fire Zoning and Life Safety Plan.

(x) Civil submittal shall include, but are not limited to, the following:

- Description of utility systems and civil works as they interface with the building including, but not limited to, finished grading and paving, fire protection, gas, water, sanitary sewer, electrical, telephone and communications systems.
- Supporting cost studies and analysis for alternative designs.
- Calculations and assumptions.

(xi) Façade and Building Maintenance systems submittal shall include, but are not limited to, where and as necessary, the following:

- Description of the various façade and building maintenance systems and details of their interface with the building including, but not limited to façade detailing, equipment storage provisions, maintenance regime and strategies.
- Supporting cost studies and analysis for alternative designs.
- Calculations and assumptions.

(xii) Consultant to determine the need based on following requirement.
The deliverables under the Schematic phase are listed below:

- Interiors and Landscape
 - All applicable deliverables and drawings as per project scope.
 - Material boards both hard and digital copies.
 - FFE Schedule and specifications..
- Elevator
 - Preliminary report concluding with selection of lift types, numbers, locations capacity and speeds presented with technical data to support recommendations.
- Acoustic
 - Preliminary report detailing acoustic aspects and material selection and criteria for all areas of the Project.
- Graphics and Signage
 - A complete full color library of signage detailing applications and sizes in each signage category.
 - Drawings detailing typical specification for each sign type including proposed materials and finishes.
 - Dimensioned layout plans for signage based on the schematic interior design layout plans.
 - Photographs (if available) of all signs proposed.
- Lighting Design
 - Schematic lighting layouts.
 - Preliminary lighting fixtures schedule including specifications, photographs, catalogues and samples adequate to demonstrate the design intent.

(xiii) Schematic Design Report which shall include the following:

- Introduction
- Executive Summary for all disciplines including without limitation: Architectural, Interior, Landscaping, Civil, Structural, Mechanical and Electrical.
- Design Updates:
 - AOR section.
 - Architectural design Overview.
 - Interior Design Overview.
 - Structural design Overview.
 - Mechanical design Overview.
 - Electrical design Overview.
 - Landscape and civil engineering.
 - Material handling and circulation.

- People movement (horizontal and vertical transportation).
 - Outline Specifications, including generic Finish Schedule
 - Functional Programme
 - Project Schedule
 - Reduced Drawings (Bound sets of A3)
 - Overview and Update of Authorities requirements for permitting purposes.
- (f) Attend meetings with TQD and other consultants to discuss the draft Schematic Design Phase documentation and prepare minutes thereof where appropriate.
- (g) Attend meetings with TQD and other consultants to discuss the VE options if required.
- (h) Amend the draft Schematic Design Phase documentation to incorporate as applicable the requirements of TQD and submit to TQD for approval purposes the final version of the Schematic Design Phase documentation. All such documentation shall be marked “Final”.

4.2.3.3 Phase.03 (c) – Detailed Design.

- (a) Commence the Detailed Design following receipt of TQD’s approval of the Schematic Design.
- (b) Attend design team meetings which to be held at weekly intervals in throughout the Detailed Design Phase. The meetings shall be chaired and minuted by the Consultant.
- (c) Based on the approved Schematic Design, fully develop the design and prepare and submit to TQD for review purposes a draft of the Detailed Design Phase documentation. All such documentation shall be marked “Draft”.
- (d) The Detailed Design Documentation shall include as a minimum:
 - Final design drawings of all floor plans and elevations.
 - Final Code Review and update requirements for permitting purposes.
 - 100% Design Development:
 - (i) Site Location: Scales vary. Metric dimensions. In this series of drawings:
 - Key plan showing the location of the new building on the block.
 - Buildings dimensionally tied down to all relevant adjacencies.
 - Key floor plans for large scale projects.
 - Street lines, property lines, setbacks, easements, light poles and other existing and proposed services.
 - Manholes and sewers, hydrants, areaways and other sub-grade spaces.
 - New and existing roads and ramps with grade elevations.
 - Enlarged plans at the retail and podium, plazas, fountains and floor entrances.

- Proposed and existing (if any) utilities.
- Site lighting.
- Areaways, vaults and other sub grade spaces, where applicable.
- Details of open stairs, railings, fences, ramps, lights and exterior furniture.

(ii) **Architectural Building Plans: Scales of 1:500, 1:200, 1:100, 1:50. Metric dimensions. In this series of drawings:**

- Building perimeter and exterior wall types are fixed
- Column sizes and grid lines are fixed
- All internal partitions are located and drawn to required dimensions.
- Doors are located with door swings.
- Doors types are either marked on the drawings or shown in schedule format.
- Finish floor elevations are marked.
- Partition types are called out and legend is provided.
- Section, elevation and detail references are marked.
- All casework is shown and called out including all wet areas.
- All rooms are named and numbered.
- All fire rated partitions are identified by the required fire resistance rating.
- Enlarged plans of core areas are worked out & dimensioned.
- All expansion joints are identified
- Roof plans showing drains and major equipment are included in the package.

(iii) **Building Elevations: Scales of 1:500, 1:200, 1:100. Metric dimensions. In this series of drawings:**

- All building elevations are shown.
- All window locations are fixed and shown.
- All floor level elevations are shown.
- All top of window elevations are marked.
- Structural gridlines are marked.
- Overall vertical dimensions and heights are indicated.
- All building materials are noted.
- All expansion joints, panel joints and control joints and reveals are indicated.
- Building sections are referenced.
- Grid lines are dimensioned.
- All materials are noted.

- Exterior equipment, rooftop stack & other elements're shown
- Enlarged elevations showing design intent of special areas are developed.

(iv) Building Sections: Scale of 1:200, 1:100. Metric dimensions. In this series of drawings:

- Sections through all major portions of building showing design concepts including vertical transportation are included
- Floor to floor and ceiling heights are indicated.
- Floor and parapet / roof level elevations are noted.
- Related wall section / details are referenced.
- Grade elevations are noted.
- Relationship to new or existing grade are noted.
- Grid lines are marked.
- Rooms / spaces, through which sections pass, are named.
- Interior elevations of major areas are shown.

(v) Wall Sections: Scale of 1:50. Metric dimensions. In this series of drawings:

- Major exterior wall sections are included.
- Foundation and perimeter treatment is shown.
- All critical dimensions are indicated.
- Wall types construction is indicated and materials called out.
- Wall sections are cross-referenced to the sections and plans.
- Mechanical penetrations are noted.
- Windows and parapets are detailed and dimensioned.
- Masonry and / or stone coursing where applicable are shown.

(vi) Details and Enlarged Plans: Scales vary. Metric dimensions. In this series of drawings:

- Typical unit layouts with dimensions and equipment called out.
- All shafts and service cores are shown and dimensioned.
- All elevators and stairs are drawn and dimensioned.
- Casework elevations and millwork sections and profiles are shown and dimensioned.
- Typical interior and exterior column covers and finishes are shown and detailed.
- Typical window head / sill / Jamb details are included.

(vii) Reflected Ceiling Plans: Scale of 1:100. Metric dimensions. In this series of drawings:

- All ceiling grids and / or pattern for finished floors are shown.
- Light fixtures are located.

- HVAC diffusers are shown.
- Relationship with partitions below are resolved and coordinated.
- Access panels, ceiling mounted tracks and all other suspended items are shown and called out.
- Exposed structure adjacent to finished ceiling is shown and called out.
- Skylights (if any) and soffits are shown and called out.

(viii) Schedules: N.T.S. In this series of documents:

- Room Finish Schedule on 11X17 Format.
- Door and Frame Schedule on 11X17 Format.
- Preliminary Hardware Schedule.
- Windows and Glazing Schedule.
- Louvres Schedule.

(ix) Structural Items, This set of documents to include:

- Foundation plans including foundation sizes footings, caissons, beams etc.
- Framing plans for upper floors including reinforcing notes or details.
- All slab openings, pits, tunnels and ramps.
- Expansion joints located and sized.
- Typical edge of slab details.
- Special conditions – dewatering, shoring, underpinning etc.
- Loads key sheet and general notes, calculations.

(x) MEP, This set of documents to include:

- All risers, shafts, chases and equipment rooms sized and located on architectural plans.
- Plumbing drawings showing mains and main branches, location of risers, and schematic system diagrams.
- LPG Gas installation diagrams.
- HVAC drawings showing supply, return and exhaust ducts, location of risers and schematic system diagram.
- Power drawings showing panel locations, main distribution and schematic system diagrams.
- Lighting drawings coordinated with architectural and mechanical drawings and shown on reflected ceiling plans.
- Telephone and PABX installation design.
- CCTV installation design including associated surveillance equipment and alarms.
- MATV installation design documents.
- All information technology installation design doc.

- Security and access control installation design.
- Fire protection and control design documentation including external hydrants and portable fire fighting equipment.
- Lightning protection.
- Television, video and audio-visual systems design.
- Equipment room plans and required pad identification.
- Louvres located, sized and coordinated with architectural drawings.
- Catalogue cuts of: proposed plumbing fixtures, sprinkler heads, light fixtures, fire alarm devices and any special equipment.
- Short form specifications.

(xi) Consultant set of documents to include:

- Interiors & Landscape
 - Full design documentation.
 - Finalized Renders.
 - Material boards both hard and digital copies of the final approval option.
- Elevator
 - Fully detailed elevator traffic study, design and specs.
- Acoustic
 - Updated report detailing acoustic aspects and material selection and criteria for all areas of the Project.
 - Mechanical system acoustic evaluation.
- Graphics and Signage Design
 - Fully dimensioned drawings, AI, PSD files to enable fabrication of all signage and graphics.
 - Specifications and schedules for all signage and graphics.
 - Location drawings identifying exact locations of all signage and graphics.
- Lighting Design
 - Fully dimensioned lighting system layouts for the Projects.
 - Detailed lighting fixture and equipment schedules accompanied by specifications, photographs, catalogues and samples adequate to show the final design intent.
 - Detailed lighting control and dimming channel schedules accompanied by specifications, photographs and samples.
 - All necessary documentation and details to enable

mock-ups and models to be produced.

(xii) Miscellaneous, This shall include the following:

- A single series of coordinated and dimensioned Plans, Elevations (Internal and External), Sections and Details, indicating the location and accurate size of all Lighting; Electrical and Data Outlets; Switches; Security, Access and HVAC Controls, Fittings and Equipment; Fire and Life Safety Equipment; Door Hardware; Signage; Plumbing Tapware, Fixtures and Fittings; Elevator Floor Indicators and Call Buttons; and the like.
- Large Scale (1:20 / 1:10 / 1:5 / 1:2) Plan, Elevation and Section Details for all design elements (entrances, reception, corridors, toilets, prayer rooms, lifts and lift lobbies) across the project, fully coordinated between all design disciplines, and as required to comprehensively document the construction of the project, its component parts and all interfaces between materials, surfaces, planes and products.
- Final Computer renderings (min 10 no.) internal, 4 external and 1 Birdseye.

Please indicate the price of additional renderings if required.

- Specifications Division.
- Architectural Specifications: Short form.
- Interior Specifications: Short form.
- Civil/ Landscape Specifications: Short form.
- Structural Specifications: Short form.
- Elevator Specifications: Short form.
- Mechanical Specifications: Short form.
- Electrical Specifications: Short form.

(xiii) Updated Design Documentation

- Updated Project description.
- Updated Project statistics.
- Programme verification.
- Design Development Report containing all of the above.
- Updated Perspective Rendering.
- Material and color selections.
- Outline Specification.
- Minutes of Design Team Meetings.
- Architectural fully dimensioned plans of all units.

(e) Attend meetings with TQD or other consultants to discuss the draft Detailed Design Phase documentation and prepare minutes thereof where appropriate.

(f) Amend the draft Detailed Design Phase documentation to incorporate as applicable the requirements of TQD and submit to TQD for approval purposes the

final version of the Detailed Design Phase documentation. All such documentation shall be marked "Final".

4.2.3.4 Phase.03 (d) – Tender Documentation and Tender Stage.

- (a) Commence the Tender, Contract and Construction Documentation Phase following receipt of TQD's approval of the Detailed Design.
- (b) Based on the Detailed Design approved by TQD, prepare all technical documentation required for tender purposes and for contract purposes including without limitation drawings, specifications and schedules.
- (c) Prepare all documentation required to construct the Project including without limitation fully detailed drawings, specifications and schedules.
- (d) Provide advice and assistance to TQD in the prequalification and selection of tenderers.
- (e) Prepare and submit to TQD for review purposes a draft of the Tender documents in the number of copies advised by TQD:
 - Specification
 - Drawings

Each such document shall be marked "Draft".

- (f) Attend meetings with TQD and other consultants to discuss the draft documents referred to in paragraph (e) above and prepare MOM.
- (g) Amend & Provide the draft documents referred to above to incorporate as applicable the requirements of TQD and submit the final version of the Tender Documents to TQD in the number of copies advised by TQD.
- (h) Prepare replies to technical queries relating to the Tender Documents raised by Tenderers during the Tender Period and pass to TQD for incorporation into an Addendum to the Tender Documents.
- (i) Review the technical aspects of Tenders received and report to TQD thereon together with recommendations.
- (j) Upon request, and if required, attend meetings of TQD's Tender Committee
- (k) Upon request, and if required, attend, and participate in Tender Clarification Meetings to be held with Tenderers following the receipt and evaluation of the Tenders including the preparation of minutes thereof where appropriate and the preparation of supplement reports for submission to TQD.
- (l) Prepare ready for issue to the Contractor all documentation required for the construction of the Project.
- (m) In preparing the Tender documents, Contract documents and documentation required for the construction of the Project the Consultant shall take care to ensure that these are complete in all respects and that there are no errors or omissions in relation thereto which may necessitate the issue of a Variation Order and/or entitle the Contractor to additional payments under the Construction Contract.

4.2.3.5 Phase.04 – Construction site supervision.

- (a) The Consultant shall provide post-contract supervision and compliance monitoring services following contract award to the successful contractor.
- (b) Review and approve contractor submittals (shop drawings, material samples,

- equipment data, method statements), process contractor RFIs, review and recommend on variation orders and change requests, maintain project correspondence and records, conduct regular progress meetings with contractor and TQD, prepare monthly progress reports with photographs and commentary.
- (c) Conduct site inspections to verify compliance with contract documents, witness testing and commissioning of building systems, review contractor quality control procedures, approve materials prior to installation, maintain defects register.
 - (d) Assist the contractor to coordinate with authorities for inspections and approvals during construction, ensure compliance with building permits and NOCs, facilitate ADCD fire life safety inspections, coordinate DOE energy efficiency compliance verification, witness authority testing and commissioning requirements, obtain completion certificates and NOCs.
 - (e) Minimum twice weekly site visits during construction phase with increased frequency during critical activities, attend contractor progress meetings, conduct coordination meetings between trades, review contractor HSE compliance, monitor construction progress against approved program.
 - (f) Review contractor construction methodology, approve temporary works proposals (if required), coordinate building systems integration and T&C of MEP systems, verify dimensional accuracy and tolerances, approve critical construction phases (structural, waterproofing, MEP rough-in, finishes).
 - (g) Monitor construction progress against approved schedule, identify delays and recommend recovery measures, track material deliveries and approvals, coordinate with TQD on any design modifications, prepare progress reports with recommendations, maintain photographic records of construction progress.
 - (h) Testing and Commissioning Oversight, review test certificates and warranties.
 - (i) Conduct substantial completion inspections, prepare snag lists and defects register, coordinate defects rectification, witness final authority inspections, review handover documentation preparation, coordinate training for TQD's facilities management team.
 - (j) Prepare weekly Progress Reports: Construction progress summary with percentage completion by trade, photographic documentation of work progress, identification of delays or issues with recommended solutions, review of contractor performance and compliance, updated project schedule and critical path analysis, cost status and variation orders summary, authority inspections and approvals status, health and safety compliance review
 - (k) Handover Support: TQD training coordination for building systems operation, facilities management documentation handover, defects liability period support and coordination, final account settlement technical review, project close-out documentation review.

5. Commercial proposal and Fees schedule

5.1 Requirements

Please provide your fee proposal using the following structure:

No.	Stage	Fee	Notes
Base Scope of Work			
1	Phase.01: Site survey, Assessments, and TDD		
2	Phase.02: Strategic Recommendations and Feasibility Analysis based on assessment findings		
Optional Scope Of Work			
3	Phase.03 (a): Concept Design		
4	Phase.03 (b): Schematic Design		
5	Phase.03 (c): Detailed Design		
6	Phase.03 (d): Tender Documentation and Tender Stage		
7	Phase.04: The post contract supervision and compliance monitoring services fees to be provided as monthly breakdown with resource allocation for projects programme. The post contract supervision and compliance monitoring services will be finalized at the end of the design stage only.		