

INITIAL SITE VISIT REPORT

Project: Detailed Assessment and Consultancy Services for Madinat Zayed Buildings – Al Dhafra Region

Subject: Initial Site Visit Assessment and Project Scope Evaluation

Date: 03 June 2026

Prepared By: Dar Al Khalij Engineering Consultancy LLC

Purpose: Initial Site Assessment and Consultancy Scope Definition Report for TAQA Madinat Zayed Facilities Modernization and Expansion Project

1. EXECUTIVE SUMMARY

An initial site visit and project scope discussion were conducted for the proposed Detailed Assessment and Consultancy Services associated with the existing TAQA facilities located in Madinat Zayed, Al Dhafra Region.

The assessment covered the following facilities:

- Administration Building (G+2)
- Customer Service Building
- Security Entrance office
- Emergency Building (Located on a separate plot)

The primary objective of the proposed consultancy assignment is to undertake a comprehensive assessment of the existing facilities and develop technically feasible solutions for modernization, refurbishment, operational enhancement, expansion requirements, authority compliance, and future sustainability of the facilities.

The visit also focused on identifying existing deficiencies, understanding operational requirements, evaluating available documentation, and establishing the preliminary scope of work required for the design and consultancy services.

2. EXISTING FACILITY CONDITIONS

Based on information provided during the site visit and visual observations, all facilities are existing buildings with an estimated age exceeding thirty (30) years.

The following general observations were noted:

Architectural and Interior Conditions

- Existing furniture, fixtures, and equipment (FF&E) are outdated and require modernization.
- Internal finishes throughout the facilities show signs of aging and require refurbishment.
- Existing toilet facilities require upgrading to comply with current operational and user requirements.
- Pantry facilities and associated support spaces require refurbishment and modernization.

MEP Services

- Existing Mechanical, Electrical, and Plumbing (MEP) systems are aged and require detailed assessment.
- Existing services may require substantial upgrading or replacement to satisfy current operational and regulatory requirements.

Documentation Constraints

- Existing building documentation is limited.
- Approved authority drawings and records are reportedly unavailable.
- Approved as-built drawings are currently unavailable.
- Site photography was restricted during the visit and therefore detailed photographic documentation could not be obtained.

These limitations will necessitate extensive verification surveys during the subsequent stages of the project.

3. ADMINISTRATION BUILDING

Existing Building Information

- Building Configuration: Ground Floor + Two Floors (G+2)
- Current Occupancy Capacity: Approximately 150 personnel

Future Operational Requirement

The Client has indicated a requirement to increase the building occupancy by approximately 100 additional personnel.

Preliminary Observations

- Existing office layouts require review and optimization.
- Existing toilet facilities require modernization and possible expansion.
- Existing support and ancillary facilities require assessment.
- Existing furniture and workspace arrangements require replacement and modernization.
- Existing electrical outlets and associated electrical infrastructure are outdated and require upgrading.

Fire and Life Safety

A significant observation during the visit was the absence of a complete firefighting system. Current provisions consist primarily of portable fire extinguishers.

Accordingly, a detailed evaluation will be required to assess:

- Fire alarm requirements.
- Firefighting system requirements.
- Life safety compliance.
- Authority requirements and code compliance upgrades.

4. CUSTOMER SERVICE BUILDING

The Customer Service Building requires comprehensive modernization and refurbishment works.

Preliminary Observations

- Existing furniture is outdated.
- Interior finishes require upgrading.
- Existing operational systems require modernization.
- Architectural enhancements are required to align with current standards.
- MEP systems require detailed review and upgrading.

The proposed consultancy scope should include full assessment and development of refurbishment proposals to improve operational efficiency and customer experience.

5. EMERGENCY BUILDING

The Emergency Building is located on a separate plot and is generally understood to be in a condition similar to the other facilities.

Preliminary Observations

- Modernization and refurbishment works are anticipated.
- Assessment of future operational requirements will be necessary.
- Functional and space utilization studies will be required.

Potential Functional Integration

During discussions with the Client, it was indicated that the operational activities currently accommodated within the Emergency Building may potentially be transferred to the proposed expansion of the Administration Building. This requirement shall be further investigated during the assessment phase and considered when evaluating future space planning and expansion options.

6. STRUCTURAL ASSESSMENT

The Client advised that previous structural and MEP assessments of the facilities have been undertaken by a specialized consultant. These reports and associated drawings are expected to be shared following project appointment, as the documents are currently considered confidential.

Proposed Structural Assessment Scope

The consultancy services may include:

- Review of existing structural assessment reports.
- Review of existing MEP assessment reports.
- Verification of previous assessment findings.
- Additional investigations and assessments where necessary.
- Evaluation of structural integrity and serviceability.
- Determination of renovation feasibility.
- Assessment of demolition and reconstruction alternatives where renovation is technically impractical or economically unjustified.

The final recommendations shall be based on technical, operational, and financial considerations.

7. SURVEY, RECORD VERIFICATION AND DOCUMENTATION

The availability of existing drawings remains uncertain at this stage. The Client indicated that certain drawings may be available and could be provided following appointment.

Current Documentation Status

- No approved authority documentation is available.
- No approved as-built drawings are available.
- Existing records are incomplete.

Required Actions

A comprehensive site verification survey will therefore be required to:

- Establish accurate building dimensions.
- Verify architectural layouts.
- Verify structural systems.
- Confirm MEP installations.
- Develop an accurate existing conditions record for future design development.

This activity will form a critical component of the consultancy services.

8. AUTHORITY APPROVALS AND REGULATORY COMPLIANCE

The project scope will include obtaining all required approvals, permits, and regulatory clearances associated with the proposed works prior to commencement of construction activities.

Further Clarification Required

Additional information is required regarding:

- Applicable approving authorities.
- Authority approval strategy.
- Existing building legalization requirements.
- NOC requirements.
- Permit requirements.
- Fire and life safety authority requirements.
- Utility authority coordination requirements.

A comprehensive approvals matrix shall be developed during the project initiation stage.

9. EXTERNAL WORKS AND SITE INFRASTRUCTURE

The project shall also evaluate external site elements and infrastructure improvements.

Potential Scope Items

- Existing parking improvements.
- Landscape enhancement proposals.
- Modernization of external areas.
- Functional site development solutions.
- Site circulation improvements.
- Boundary wall repair and rehabilitation works.

Boundary Wall Assessment

During the site visit, visible structural cracking was observed in portions of the existing boundary wall surrounding the site.

A detailed engineering assessment is therefore required to determine:

- Causes of cracking.
- Structural condition of affected sections.
- Repair methodology.
- Strengthening requirements.
- Rehabilitation requirements.
- Long-term maintenance recommendations.

Complete treatment and restoration of affected boundary wall sections should be considered as part of the overall project scope.

10. SECURITY AND ELV SYSTEMS

A comprehensive review of security and Extra Low Voltage (ELV) systems is required across all facilities.

Proposed Requirements

- CCTV surveillance coverage for all buildings.
- CCTV coverage of external areas.
- Assessment of existing security coverage gaps.
- Development of integrated security system design.
- Provision of a dedicated CCTV monitoring and control room.
- Review of communication and monitoring infrastructure requirements.

The proposed design shall align with current security standards and operational requirements.

11. KEY CONSULTANCY SCOPE OF WORK

The anticipated consultancy scope shall include, but not necessarily be limited to, the following services:

Assessment and Evaluation

- Existing condition assessment review.
- Structural assessment review.
- Boundary wall structural assessment.
- Operational requirements assessment.

Design and Engineering Services

- Architectural modernization proposals.
- Interior refurbishment design.
- MEP system upgrading proposals.
- ELV system design.
- CCTV and security control room design.
- Fire and life safety compliance recommendations.

Feasibility Studies

- Renovation feasibility assessment.
- Demolition and reconstruction feasibility assessment.
- Cost-benefit evaluation of alternative solutions.

Regulatory and Tender Services

- Authority approvals and permitting.
- Preparation of design drawings.
- Technical specifications.
- Cost estimates.
- Tender documentation.

12. CONCLUSION

Based on the information currently available, the project involves the comprehensive assessment, modernization, refurbishment, authority compliance, and potential expansion of four existing facilities within Madinat Zayed.

The facilities are generally aged, with limited available documentation and significant requirements for modernization of architectural, structural, MEP, security, and operational systems.

Additionally, structural concerns relating to the existing boundary wall and the requirement for a comprehensive CCTV surveillance system with a dedicated monitoring and control room have been identified as part of the extended project scope.

The consultancy services shall evaluate renovation, refurbishment, expansion, demolition, and reconstruction options where applicable and provide recommendations based on:

- Structural condition.
- Operational requirements.
- Regulatory compliance.
- Technical feasibility.
- Financial viability.
- Long-term sustainability objectives.

Existing assessment reports, available drawings, and project documentation are expected to be made available following project appointment, as these documents are currently confidential.

Furthermore, site photography was restricted during the visit and therefore visual records of the existing facilities could not be obtained.

Based on available information and the plot dimensions observed from publicly available mapping sources, the overall site configuration has been preliminarily reviewed and will be further verified during the detailed survey stage.

SITE AERIAL VIEW – TAQA MADINAT ZAYED FACILITIES

